

REMORA: Autonomous boat capable of powering and operating aerial and underwater drones for offshore windfarm inspection



Vasu Kaker¹

vasuk@mit.edu

Supervisor(s): Douglas Hart¹

1. Dept of Mechanical Engineering, Massachusetts Institute of Technology


From Knowledge
to Competitiveness

Portugal-US Partnerships 2026 Summit

MIT Portugal
Program


Earth Systems: Oceans to Near Space

Motivation



- >15,000 offshore wind turbines. Power for 60 million homes.
- 30% of the world's oil/gas is produced offshore
- Without frequent inspection, these structures are corroded away.
- Current inspections are expensive – boat, personnel, fuel means simple aerial drone/underwater ROV inspection costs \$15k/day.

Overview of REMORA



REMORA consists of:

- Boat:** 15ft autonomous electric vessel
- ROV:** System to power, operate, launch, and recover a tethered underwater vehicle
- Drone:** Dock where drones land, recharge, take off, and are stored

Benefits of REMORA


	REMORA Inspection	Current Inspection
Humans Needed	1 (onshore)	>5
Boat	15ft unmanned vessel	>50ft Crew Transfer Vessel
Daily cost	\$2k / day	\$15k / day

Boat



Boat autonomy uses Jetson Orin / Pixhawk 6X. Electrically powered via lithium-ion batteries. Using Starlink, we are able to control this boat from anywhere in the world.

Remotely Operated Vehicle (ROV)



1. ROV LARS

2. A Frame lowers ROV

3. Reel unwinds, lowers ROV into water

Reel

Linear Actuator

A Frame

ROV


4. ROV deployed. Reel slip ring gives power/comms

Drone: Precision Landing




Steps in Landing:

- Drone approaches boat using GPS
- Drone spiral searches for April Tag array
- Drone uses April Tag Array to estimate its relative position and land



Drone Dock: Steps in Operation



1. Roof opens

2. Drone lands

3. Moving bar secures, charges drone

4. Roof closes

Retractable Roof

April Tags

Drone

Landing Pad

Clamping Bar

Drone Side: Passive magnet, charging pads

Bar Side: Electromagnet, charging pads

Conclusion

Demonstrated:

- Dry test of boat EE/SW
- Autonomous precision landing of Drone in winds up to 8 m/s with 10" accuracy,
- Development of robust drone station
- Validation of ROV LARS system on Charles River

Next Steps:

- Integrate drone dock, boat electronics, and ROV LARS onboard
- Test full system in realistic Sea States

Funded by:

MIT Portugal
Program

MIT
MECHE